



Republic of the Philippines
Department of Education

15 DEC 2017

DepEd ORDER
No. 64, s. 2017

**ESTABLISHING THE MINIMUM PERFORMANCE STANDARDS AND SPECIFICATIONS
FOR DEPED SCHOOL BUILDINGS**

To: Undersecretaries
Assistant Secretaries
Bureau and Service Directors
Directors of Services, Centers and Heads of Units
Regional Secretary, ARMM
Regional Directors
Schools Division Superintendents
Public and Private Elementary and Secondary School Heads
All Others Concerned

1. The Department of Education (DepEd) issues this DepEd Order on **Establishing the Minimum Performance Standards and Specifications (MPSS) for DepEd School Buildings** to guide the Department and other stakeholders in the preparation of plans—architectural, structural, electrical, fire protection and sanitary—to ensure the comfort and safety of the would-be occupants of the school buildings.
2. A well-designed school building, that considers ergonomics, anthropometrics, thermal comfort, illumination, ventilation, acoustics, color, and compliance with the law, contributes to improved student performance, and makes a lasting impression on the community with regard to importance of education.
3. All DepEd Orders and other related issuances, rules and regulations that are inconsistent with these minimum performance standards and specifications are hereby repealed, rescinded, or modified accordingly.
4. This Order shall take effect immediately upon its approval.
5. Immediate dissemination of and strict compliance with this Order is directed.

LEONOR MAGTOLIS BRIONES
Secretary

Encl.: As stated

Reference: DepEd Order No. 69, s. 2003

To be indicated in the Perpetual Index
under the following subjects:

LOGO
POLICY
PROGRAMS
RULES AND REGULATIONS

SEAL
SCHOOLS
SCHOOLBUILDING

MCR/DO-establishing the Minimum Performance Standards...
0935-October 2, 2017/11-6

MINIMUM PERFORMANCE STANDARDS AND SPECIFICATIONS (MPSS) FOR DEPED SCHOOLBUILDINGS

I. Rationale

With the passage of Republic Act. No. 9155, otherwise known as the "Governance of Basic Education Act ", the Department of Education (DepEd) was vested with the authority, accountability and responsibility of ensuring access, promoting equity, and improving the quality of basic education.

With the issues on education becoming more complex with the passage of time, there is a need to synchronize, harmonize, and unify existing provisions on order to fast track the DepEd's delivery of basic services.

This Order specifically aims to establish the acceptable minimum performance standards and specifications (MPSS) in the design of DepEd schoolbuildings, whether single-storey, medium-rise or high-rise to be constructed in the various school sites across the country. The MPSS will serve as the basic instrument of the Central and field offices as well as the stakeholders towards the standardization of schoolbuildings wherever schools are located. The Department believes that quality schoolbuildings contribute greatly to the attainment of education goals.

II. Background

It is not uncommon at the Education Facilities Division (EFD) Office that calls are received seeking answers to queries such as the classroom size in public schools, how to establish a pre-school, as well as what are acceptable building materials and modifications to a programmed schoolbuilding. In addition to these are communications forwarded through letters, e-mail and the like, which may originate from an ordinary resident or a high ranking official, on issues pertaining to schoolbuildings.

These issues and concerns build up for the EFD Technical Team, particularly the Planning and Design Unit, which necessitates the formulation of a workable means to disseminate information not only to the field offices but also to the public interested in DepEd's School Building Program. With modern

technology impinging on the architecture and engineering of future school buildings, the EFD faces the challenge of releasing/issuing a mini-literature establishing the minimum specification and standards for schoolbuildings guided by the principle of comfort, safety, and security of occupants at all times.

III. Scope of Policy

This Deped Order provides for the establishment of minimum performance standards and specifications (MPSS) in the design of the Department's schoolbuildings whether to be implemented by co-partners in government (DPWH) or by non-government agencies/entities, such as foreign-assisted school building projects. It covers such elements as architectural design standards, structural design standards as well as electrical design standards which may concern DepEd stakeholders within and outside the DepEd CO.

IV. Policy Statement

1. A well-designed schoolbuilding (which considers ergonomics, anthropometrics, thermal comfort, illumination, ventilation, acoustics, color and compliance with laws) contributes to improved student performance and makes a lasting impression on the community with regard to the importance of education.

2. The Department established the Minimum Performance Standards and Specifications (MPSS) in the design of DepEd schoolbuildings to guide the Department and other stakeholders constructing schoolbuildings in the preparation of plans - architectural, structural, electrical, and sanitary - to ensure the comfort and safety of the would-be occupants of the schoolbuildings.

V. Architectural Design Standards

a. Classroom Size

The size of the classroom for elementary and secondary schools must be 7.00 meters in width/depth x 9.00 meters in length or 9.00 meters in width/depth x 7.00 meters in length measured from the centers of the walls.

b. Windows

- 1) The windows must be of bilateral fenestration (transparent or translucent), operable louver type. The window must allow the entry of daylight even if it is closed.
- 2) The total area of window openings must be at least 10.00 square meters to provide for natural ventilation and illumination.
- 3) The window sill must not be lower than 0.60 meter for single-storey buildings or higher than 0.90 meter for multi-storey buildings from the finished floor line (FFL).
- 4) The minimum height of the fixed louver or transom window above the operable windows is 0.30 meter.
- 5) The window panels, when opened, must not be an obstruction along the corridor.
- 6) The window metal frames and jalousie holders must be sturdy enough to withstand vandalism.

c. Doors

- 1) There shall be two (2) doors for every classroom.
- 2) The swing-out should be 180 degrees.
- 3) The doors must be 0.90 meter in clear width and 2.10 meters in clear height.
- 4) The doors must withstand normal wear and tear and shall be provided with keyed lever-type locksets.

d. Floor

- 1) The floor must be of non-skid finish (grayish color).
- 2) The classroom FFL should be higher than the corridor FFL by 25 millimeters.
- 3) The first floor finish elevation must not be less than 225 millimeters and 325 millimeters for single-storey and multi-storey school buildings, respectively. The elevation may be increased depending on the history of flood level.
- 4) A ramp must be provided with a maximum slope of 1:12 in compliance with the Accessibility Law (B.P. No. 344), of non-skid finish and properly labeled.

e. Ceiling

- 1) The ceiling must be a drop-type ceiling.
- 2) The clear height of rooms from FFL to the finished ceiling line (FCL) must be at least 2.70 meters.
- 3) Materials to be used for the ceiling must provide thermal comfort inside the classroom.
- 4) Maintenance access to the ceiling cavity must be through the corridor.

f. Roofing

- 1) The roofing material must be adequately protected from rust/oxidation, salt air, acid rain, or other sources and forms of corrosion. If made of metal, the roofing sheets shall be of 0.40 mm base metal thickness (BMT) and securely fastened to the roof frames.
- 2) For single-storey schoolbuildings, gutters may not be included however, a properly sloped trench drain on both sides must be provided.
- 3) For multi-storey schoolbuildings, the roof must be provided with concrete gutter and eaves which shall be at least 1.10 meters from the corridor.

g. Partitions

The partitions must be from floor to ceiling.

h. Corridors

- 1) The corridor for single-storey schoolbuildings shall not be less than 1.50 meters.
- 2) For multi-storey schoolbuildings the corridors must not be less than 2.50 meters and should be provided with steel railings at a height not less than 1.50 meters.

i. Stairways

- 1) For multi-storey schoolbuildings, concrete stairs must have a width of not less than 1.50 meters.
- 2) Number of stairways per schoolbuilding shall comply with the requirements stipulated in the National Building Code of the Philippines (NBCP).
- 3) Handrails with steel railings must be provided.

j. Fire Protection

- 1) All schoolbuildings shall comply with R.A. No. 9514, otherwise known as the Fire Code of the Philippines (FCP) and its latest Implementing Rules and Regulations (IRR). The requirements shall include a fire alarm system, a standpipe system, pressure and gravity tanks, hose boxes/reels, extinguishers and other firefighting equipment, including an automatic sprinkler system (NFPA 13). In addition, 3-storey and 4-storey school buildings should be compliant with NFPA 25.
- 2) Fire escapes must be provided for multi-storey schoolbuildings following the requirements of the Fire Code of the Philippines.

k. Chalkboard

The classroom must be provided with a built-in curved chalkboard measuring 4.88 meters wide by 1.22 meters tall, with mounting heights and specifications as per DepEd standards.

l. Painting

- 1) The standard paint/color schedule of DepEd schoolbuildings shall be as follows:

Element	DepEd MPSS Color Scheme	Paint / Color Schedule	Masonry Paint (Latex)	Paint for Wood, Metal, etc.
ROOFING and ACCESSORIES (if introduced)	Foam Green	Foam Green	N / A	
DOORS	Palmyra Green	Temptation		
COLUMNS and BEAMS	Beige (Light shade)	Yellow Rain		
EXTERIOR WALL	Beige (Very Light shade)	Crisp Ecru	Semi-gloss Latex	Quick-dry Enamel (QDE) Semi- gloss
INTERIOR WALL	Beige (Lightest shade)	Bright Wonder		
CEILING (suspended or slab / stair slab soffit)	White	White		
GRILLS and RAILINGS	Palmyra Green	N / A		
BASEBOARD	Beige (Lightest shade)	N / A		
FLOOR FINISH (Interior and Exterior)	Concrete Plain Cement Non-skid finish (Grayish color)	N / A	N / A	N / A

*Website : www.pantone.com/pages/paint/paintselector.aspx#paints
palettes

- 2) Paint materials for internal finish must be independently certified lead-safe paints/coatings.
- 3) All new schoolbuildings should follow the standard color scheme above, except in the following cases:

- i. A different dominant color scheme already exists. In such cases, the dominant color scheme may be applied.
 - ii. Designs and/or accents depicting local culture or school approach are practiced. In such cases, the same design/accents may be adopted.
 - iii. In both cases above, no additional cost may be charged.
- 4) No new design, accent, or color scheme different from what is hereby prescribed and/or from what already predominantly exists under Item 3 above may be proposed/introduced.
- 5) There is a need to ensure, as far as practicable, the uniformity of all public schoolbuildings essentially to provide an environment for educational activities, and effective teaching and learning. At the same time, the DepEd encourages and promotes regional diversity and cultural identity.

m. Roof Markings

Roof Markings shall be painted on the main building or the tallest building of the school. It shall include only the DepEd logo and School ID Number.

Details and specifications shall be as follows:

Roof Marking	Size	Color
DepEd Logo <i>*Refer to DepEd Order No. 69, s. 2003 entitled DepEd Logo</i>	3.80 m Height 7.60 m Length	Existing DepEd Logo Design
School I.D. Number	2.00 m Height 0.30 m Thick	Blue with Color White Outline

*Note: Distance between the DepEd Logo and the School I.D Number shall be at least **2.00m***

n. Wall Markings

- 1) All walls must be free from any markings, except the following which may be painted on separate prominent places:
- i. DepEd Name, Seal, Logo, Mission, Vision and Core Values
 - ii. Portraits and Sayings of National Heroes
 - iii. Name, ID, and Location of school.

- 2) An interior wall section may be selected and dedicated for the recognition of sponsors, donors, and other school partners, provided that the recognition material shall follow a standard metal plaque format that will be mounted on the wall.

o. Ventilation

Natural ventilation shall be primarily supplied by the windows and vents. Artificial ventilation inside each classroom shall be supplied by two (2) units of oscillating ceiling fans.

p. Illumination

Illumination falling at desk or arm rest should be taken with combined artificial and natural lighting. Illumination at all staircases and fire exit stairs shall comply with R.A. No. 9514 and its IRR.

VI. Structural Design Standards

- a. The structural design must be in accordance with the revised IRR of the 1977 NBCP and the latest edition of the National Structural Code of the Philippines (NSCP), Volume 1, 2010.**

b. Classification of Structure

In accordance with the NSCP, buildings under the Project shall be designed in accordance to the classification, based on the nature of occupancy, of "Essential Facilities."

c. Wind Load

For all schoolbuildings, the roofing and walls shall be designed to withstand a minimum BASIC wind speed (as defined in Sec. 207 of the NSCP) of 250 kilometers per hour (kph). The year-round effects of the southwest monsoon ("habagat") wind and the northeast monsoon ("amihan") wind as well as of the easterly winds must be taken into consideration due to the extensive damage these may cause to roofing, walls, and fenestrations.

A Wind Importance Factor (WIF) of 1.15, based on the NSCP, shall be used.

The structure should be fully sealed against rainwater intrusion during typhoons and heavy rains to protect sensitive materials and equipment. Doors and windows should be fully sealed against strong vertical and lateral rains.

d. Seismic Load

For all schoolbuildings, the structure shall be designed to withstand earthquakes for Seismic Zone 4 with a corresponding Seismic Zone Factor of 0.4, or as otherwise specified in the NSCP.

A Seismic Importance Factor (SIF) of 1.5 shall be used.

As the FFL shall be elevated to 0.20 meter above the level of flood indicated/identified in the Site Appraisal Reports (SAR), the use of "containment wall" is prescribed to ensure the safety of the structure during the rainy season.

e. Live Loads

The minimum occupancy or live loads shown in the table below shall be used in the design.

Live Loads

Structure Part	Live Load
Classrooms	1.9 kPa
Corridor / Stairs	4.8 kPa
Roof	1.0 kPa

Note: kPa = kilopascals

f. Design Life

The **schoolbuilding and its structure** shall have a design life of at least twenty-five (25) years.

g. Building Foundation

The foundation shall be designed for a net allowable soil bearing pressure of 96 kPa (2,000 pounds per square foot or psf). Consistent with

best practices, the Proponent shall undertake the prior appropriate studies/investigations for use as basis/bases for the foundation and structural design of each Sub-Project.

h. Wall Vibration

Walls must not unduly vibrate due to impact caused by any part of an adult human body and must neither be dented nor punctured by deliberate punches or kicks by adult humans.

VII. Electrical Design Standards

The electrical design must be in accordance with the latest edition of the Philippine Electrical Code (PEC). It must be provided with the basic electrical power and lighting layout, general notes, riser diagram, single line diagram, legends and symbols, load schedule and auxiliary layouts.

a. Lighting and Fixtures

- 1) Each classroom of dimension 7m x 9m or 9m x 7m must be provided with at least six (6) units of double T-5 36 watts fluorescent lamp with reflector or a minimum of 104 Lumens per Watt (LPW).
- 2) A duplex convenience outlet (CO) of the grounding type must be provided on each windowless side of the classroom.
- 3) Two ceiling outlets for ceiling fans for every classroom must be provided.

b. Wires and Wiring Devices

- 1) Wires shall be properly designed in accordance with Article 3.10 and the grounding system shall conform to Article 2.50 of the PEC.
- 2) Wiring devices must be of modern type and approved for both location and purpose.
- 3) Service Entrance wires for a standard 7m x 9m or 9m x 7m described above must have a size of 8.0 sq.mm minimum and properly protected by circuit breaker protection.

c. Roughing-ins

Service Entrance

The service entrance shall be at least 1.60 meters above the natural grade line (NGL) or 0.30 meter above the established high flood level, whichever is higher.

VIII. Sanitary and Plumbing Design Standards

a. Provision of Toilets and Sanitary Facilities

Toilets and sanitary facilities shall be in accordance with the Plumbing Code and the Sanitary Code of the Philippines.

b. Waste and Vent Line Piping System

The drain, waste, and vent line piping system must be aligned with the American Society for Testing and Materials (ASTM) D-2729, International Standards Organization (ISO) 4435 and ISO 3633.

c. Waterline Piping System

The system must be aligned with the Deutsche Industrie-Norm (DIN) 1988 for Polypropylene Random Copolymer (PP-R) type 3 pipe and ASTM A53 / A53M. The system must provide for a waterline service entrance.

d. Plumbing Fixtures

These must be aligned with the American National Standards Institute (ANSI) / American Society of Mechanical Engineers (ASME), A112.19.4m, A112.19.3, A112.19.5.

e. Drainage System

The storm drainage system must be sized in consideration of the rainfall intensities, slope, and roof areas of the schoolbuildings. Provision shall be made for the future installation of rainwater collection system in compliance with R.A. No. 6716 "An Act Providing for the Construction of Water Wells, Rainwater Collectors, Development of Springs and Rehabilitation of Existing Water Wells in all *Barangays* in the Philippines".

f. Septic Vault

All concrete septic tanks, if used as the sanitation solution, shall be protected from corrosion by coating with an approved bituminous coat or by other acceptable means.

IX. Mechanical / Fire Protection Design Standards

All Mechanical System equipment and installation mentioned shall conform to the provisions of the Mechanical Code of the Philippines, latest edition.

X. MONITORING AND EVALUATION

- Expected Outcome

Comfortable and safe school children in schoolbuildings turned over and accepted by DepEd from government or private implementers.

- Success Indicators

All schoolbuildings constructed are compliant with the Minimum Performance Standards and Specifications (MPSS) for schoolbuildings as mandated in this DepEd Order.

- Office in-Charge of M&E per governance level:

Governance Level	Offices/Actors for M & E	Roles/ Duties and Responsibilities
Central Office Level	<ul style="list-style-type: none">• Office of the Undersecretary for Administration (OUA)• Education Facilities Division (EFD)	<ul style="list-style-type: none">• Provides policies to guide the operations of the offices under it• Among others, develop appropriate standards and designs for education facilities;• Monitor the status of implementation (on-going/completed) of the different infrastructure programs and projects and provide status updates to

	<ul style="list-style-type: none"> • Area Managers • Office of the Secretary/ Undersecretaries (DPWH) 	<p>management and other stakeholders;</p> <ul style="list-style-type: none"> • Monitor compliance of the Central, Regional and School Division Offices (CO, RO's, SDO's) with the prescribed implementation guidelines, design and timelines; assist in the resolution of implementation issues and concerns; and manage risks that may affect the timely implementation of the projects • Receive and evaluate Narrative Site Inspection Reports for further evaluation • As per Memorandum of Agreement (MOA) between the DPWH and DepEd on the implementation of the School Building Program, specifically, the Basic Educational Facilities Fund (BEFF), observe the Minimum Performance Standards and Specifications (MPSS) and Harmonized Standard Regional Costing in the implementation of projects • Ensure the construction of complete school buildings (feature and subsidiary works enumerated in the MOA) • Conduct Joint Punch Listing Inspection to determine items of work that need to be rectified by the contractor • Conduct joint post technical inspection activities within the defects and liability
--	---	---

		period
Regional Level	<ul style="list-style-type: none"> • Regional Directors • Regional Engineers 	<ul style="list-style-type: none"> • Lead the Inspectorate Team in the monitoring and evaluation of construction/ repair projects
Division Level	<ul style="list-style-type: none"> • Schools Division Superintendent (SDS) • DPWH District Engineering Office (DPWH-DEO) • Division Engineer and Project Engineer 	<ul style="list-style-type: none"> • Concur with the Program of Works (POWs) prepared by the DPWH District Engineering Office • Assume all the duties and responsibilities relating to project implementation pursuant to R.A No. 9184 • Implement projects until completion • Submit Final Report to DepEd before the issuance of the corresponding Certificate of Completion (COC) and Certificate of Project Acceptance (CoPA) • Conduct site inspection during construction phase and punch listing of substantially completed (90%) projects
School Level	<ul style="list-style-type: none"> • School Head (Principal, Teacher-In-Charge) with Parent - Teachers Association (PTA) 	<ul style="list-style-type: none"> • Accepts completed school buildings • Check items based on approved Program of Works (POW)

- **Mechanics and Timetable for Progress Monitoring and Evaluation**
Based on the timetable submitted by the Project Implementor, DepEd Engineers (Regional, Division, and Project Engineers) shall coordinate and prepare schedule of visits to monitor schoolbuilding projects.
- **Feedback Mechanisms**
All feedback relayed to DepEd are referred to the office concerned for reply/action as necessary.

XI. REFERENCES

- Memorandum of Agreement (MOA) between the DepEd and DPWH On The Implementation of CY 2017 Basic Educational Facilities Fund (BEFF) dated March 20, 2017
- DepEd Order No. 69, series 2003 entitled DepEd Logo
- National Building Code of the Philippines (NBCP) and its revised Implementing Rules and Regulation (IRR)
- National Structural Code of the Philippines (NSCP), latest edition
- Philippine Electrical Code (PEC), latest edition
- Plumbing Code of the Philippines, latest edition
- Sanitary Code of the Philippines, latest edition
- Mechanical Code of the Philippines, latest edition
- Fire Code of the Philippines (R.A No. 9514) and its revised Implementing Rules and Regulation (IRR)

Particulars	Cost	Period Constructed	Paid By (DPWH, DO, RO, Others)
Construction of 1 STY, 2 CL Federation of Filipino Chinese Chamber of Commerce and Industry Inc. (FFCCCI)	476,190.60		Private Sector Funded
Construction of 1 STY, 5 CL FVR 2000	954,083.35	2000 DepEd Budget	fvr 2000 5 190816.67 per room
Construction of 1 STY, 5 CL FVR 2000	954,083.35	2000 DepEd Fund	fvr 2000 5 190816.67 per room
Construction of 1 STY, 1 CL Federation of Filipino Chinese Chamber of Commerce and Industry Inc. (FFCCCI)	444,444.56	1995 Private Sector Funded	500k BOD Bldg in 1995 (7m x 9m) 1 7936.51 per sqm room size: 8x7
Construction of 1 STY, 1 CL Industrial Arts Building	395,000.00	2005 DepEd Budget	1
Construction of 1 STY, 1 CL Pre-School / Kindergarten Building	607,021.40	2011 DepEd Budget	1 2011 unit cost of deped bldg 607021.4
Construction of 2 STY, 4 CL DEPED STANDARD BUILDING		2020 DEPED BUDGET	4 for verification w/ dpwh

Construction of 1 STY, 1 CL BOD - DPWH BUILDING	500,000.00	1995	DEPED BUDGET	1 school record
Construction of 1 STY, 3 CL JICA- TRSBP	4,048,584.36	1997	JICA	3
Construction of 4 STY, 12 CL DEPED STANDARD BUILDING	42,538,772.62	2018	DEPED BUDGET	12 CO
Construction of 1 STY, 1 CL FVR 2000 BUILDING	190,816.67	1999	DEPED BUDGET	tvr 2000 1 190816.67 per room
Construction of 2 STY, 2 CL DEPED STANDARD BUILDING	790,000.00	2004	DEPED BUDGET	2 deped bldg in 2005 395k per cl
Construction of 3 STY, 6 CL LGU Building	6,686,049.63	2014	City Fund	6 school record
Construction of 3 STY, 6 CL LGU Building	6,400,000.00	2015	City Fund	6 school record
Construction of 2 STY, 4 CL DepEd Standard School Building	6,298,664.77	2015	DepEd Budget	4 CO
Construction of 1 STY, 1 CL Bagong Lipunan School Building	323,900.00	1975	DepEd Budget	bagong lipunan bldg in 2019 1 323,900.00
Construction of 1 STY, 1 CL Bagong Lipunan School Building	323,900.00	1975	DepEd Budget	bagong lipunan bldg in 2019 1 323,900.00
Repair of Various School Building (on going demolition)	397,558.04	2016		school record

Construction of 2 STY, 6 CL LGU Building	7,486,959.94	2020	USB	6
Construction of 1 STY, 6 CL Federation of Filipino Chinese Chamber of Commerce and Industry, Inc. (FFCCCI) School Building		1994	FFCCCI	6 no record
Construction of 3 STY, 6 CL DepED Standard School Building	10,417,131.51	2016	DPWH	6 CO
Construction of 2 STY, 6 CL School Building	8,089,017.97	07/30/2020 to 04/08	LGU	6 school record
Construction og 4STY 8CL	25,795,047.81	2017	DEPED BUDGET	8 CO
Construction og 4STY 12CL	30,948,786.90	2017	DEPED BUDGET	12 CO
Construction og 4STY 8CL	17,018,604.02	2017	DEPED BUDGET	8 CO
Construction og 4STY 8CL	16,839,680.74	2017	DEPED BUDGET	8 CO
Construction og 4STY 12CL	31,140,220.88	2017	DEPED BUDGET	12 CO
Construction og 4STY 8CL	16,815,859.74	2017	DEPED BUDGET	8 CO
Construction og 4STY 8CL	16,899,328.44	2017	DEPED BUDGET	8 CO

Construction og 4STY 12CL	31,253,400.65	2017	DEPED BUDGET	12 CO
Construction of 1 STY, 1 CL Home Economics Building	1,563,820.00	2015	DepEd budget	2015 deped bldg cost per rm 1 1563819.688
Construction of 1 STY, 6 CL FVR 2000 Builiing	1,144,900.02	2000	DepEd Budget	fvr 2000 6 190816.67 per room room size: 7x7
Construction of 1 STY, 1 CL Deped Standard School Building	395,000.00	2005	DepEd budget	1
Construction of 2 STY, 4 CL Malksi Building	530,287.50	2008	DepEd budget	4
Construction of 1 STY, 1 CL DepEd Modified School Building	1,800,000.00	2019	DepEd budget	1 school record, DPWH
Construction of 1 STY, 1 CL Deped Standard School Building	607,021.36	2011	DepEd budget	2011 deped bldg cost per rm 1 607021.3575
Construction of 1 STY, 5 CL Remulla Building	2,659,789.60	2013	LGU	rm - - - 5 531957.92
Construction of 4 STY, 12 CL Deped Buillding Type 2018	24,514,577.98	2018	DepEd budget	12

7	Construction of 1 STY, 3 CL Gabaldon School Building	6,111,523.17	1914	DepEd Budget	3 DO Gabaldon Rehab Project
	Construction of 2 STY, 4 CL DepEd Standard School Building	4,932,807.35	2012	DepEd Budget	4
	Construction of 2 STY, 2 CL OGR Building Type	1,063,915.84	2014	City Fund	2
	Construction of 2 STY, 10 CL Public-Private School Infrastructure Project (PSIP School Building)	26,086,692.15	2015	DepEd Budget	10 PSIP CO
	Construction of 2 STY, 6 CL Public-Private School Infrastructure Project (PSIP School Building)	11,270,258.27	2015	DepEd Budget	6 PSIP CO
	Construction of 1 STY, 3 CL JICA - Educational Facilities Improvement Program (EFIP)	4,048,584.36	1997	JICA	3
	Construction of 2 STY, 6 CL Local School Building	550,000.00	2006	City Fund	6
	Construction of 1 STY, 1 CL DepEd Standard School Building	684,573.41	2011	DepEd Budget	1
	Construction of 1 STY, 2 CL DepEd Standard School Building	1,058,938.61	2011	DepEd Budget	2 similar record, cnhs

Construction of 1 STY, 1 CL Pre-School/Kindergarten Building	607,021.36	2013	DPWH
Construction of 1 STY, 1 CL DepEd Standard School Building	607,021.36	2013	DepEd Budget
Construction of 1 STY, 1 CL School Clinic	1,349,528.12	1997	Others (PTA)
Construction of 1 STY, 1 CL Pre-School/Kindergarten Building	607,021.36	2010	DepEd Budget
Construction of 1 STY, 1 CL CDF/PDAF	395,000.00	2005	PDAF
Construction of 2 STY, 6 CL Public-Private School Infrastructure Project (PSIP School Building)	11,270,258.27	2015	DepEd Budget
Construction of 4 STY, 20 CL DepEd Standard School Building S. Paredes Type Building	47,884,608.68	2019	DepEd Budget
Construction of 2 STY, 8 CL Totie S. Paredes Type Building	6,400,000.00	2010	City Fund
Construction of 2 STY, 6 CL Public-Private School Infrastructure Project (PSIP School Building)	11,270,258.27	2014	DepEd Budget

2011 deped bldg cost per rm
1 607021.3575

	Construction of 2 STY, 6 CL Public-Private School Infrastructure Project (PSIP School Building)	11,270,258.27	2014 DepEd Budget	6 PSIP CO
	Construction of 2 STY, 6 CL DepED Modified School Building (7 x 7)	3,175,000.00	1996 DepEd Budget	deped bldg in 1991 6 3,175,000.00
	Construction of 3 STY, 6 CL LGU	10,089,624.38	2021 City Fund	6 school record
	Construction of 1 STY, 2 CL LGU		2021 City Fund	2 Igubldg in 2014 2 1063915.84
	Construction of 1 STY, 2 CL LGU		2021 City Fund	2 Igubldg in 2014 2 1063915.84
8	Construction of 2 STY, 4 CL HOME ECONOMICS BUILDING	1,580,000.00	2005 DEPED FUND- Major Repair	4
	Construction of 3 STY, 6 CL REMULLA BUILDING TYPE	13,000,000.00	LOCAL FUND	6 school record
	Construction of 3 STY, 15 CL DPWH BUILDING	21,383,013.45	2016 DEPED FUND	15 CO
	CONSTRUCTION OF COVERED COURT & STAGE	14,000,000.00	2018 LOCAL FUND	school record
9	Construction of SCHOOL STAGE		2019 CITY LGU	

	Construction of 2 STY, 4 CL DEPED STANDARD BUIDING	14,918,543.58	2021 DPWH	4 CO
	Construction of 2 STY, 4 CL DEPED STANDARD BUIDING	15,129,730.00	2021 DPWH	4 CO
10	Construction of 1 STY, 5 CL TOTIE PAREDES TYPE BUILDING	458,333.33	2004 CITY BUDGET	Igu bldg in 2006 unit cost 5 91666.66667
	Construction of 1 STY, 4 CL TOTIE PAREDES TYPE BUILDING	366,666.67	2005 CITY BUDGET	Igu bldg in 2006 unit cost 4 91666.66667
11	Construction of 1 STY, 2 CL FFCCCI	888,889.12	2007 FFCCCI	500k BOD Bldg in 1995 (7m x 2.9m) 7936.51 per sqm
	Construction of 2 STY, 6 CL Paredes Building	538,187.50	2002 City Fund	6
	Construction of 2 STY, 2 CL Maliksi Type Building	790,000.00	2006 Provincial Fund	2 deped bldg in 2005 395k per cl
	Construction of 4 STY, 12 CL DepEd Standard School Building	22,314,343.62	2018 DepEd Budget	12 CO
	Construction of 2 STY, 4 CL DepEd Standard School Building	6,298,664.77	2015 DepEd Budget	4 CO

4 CO

12	Construction of 1 STY, 6 CL GABALDON SCHOOL BUILDING	587,269.66	1911	DEPED BUDGET	6
	Construction of 2 STY, 6 CL LGU SCHOOL BUILDING	7,486,959.94	2019	CITY FUND	6 interpolation of 2018-2020 lggu bldg
	Construction of 1 STY, 1 CL ABAYA TYPE	1,800,000.00	2017	CDF	1 2019 deped bldg
	Construction of 2 STY, 7 CL LGU SCHOOL BUILDING	5,600,000.00	2008	CITY FUND	2009 lggu bldg cost per rm 7 800000
	Construction of 2 STY, 2 CL HOME ECONOMICS BUILDING	1,600,000.00	2009	CITY FUND	2009 lggu bldg cost per rm 2 800000
	Construction of 3 STY, 6 CL DPWH-BOD BUILDING	10,417,131.51	2019	DEPED BUDGET	6 CO
	Construction of 4 STY, 8 CL DEPED STANDARD SCHOOL BUILDING	14,628,869.01	2015	DEPED BUDGET	8 interpolation of 2016 6 cl and 12 cl deped bldg
	Construction of 1 STY, 3 CL FVR 2000 Building	572,450.01	2000	DepEd Budget	fvr 2000 3 190816.67 per room
	Construction of 1 STY, 3 CL Army Type School Building	971,700.00	1957	DepEd budget	3 bl bldg cost 323900

Construction of 2 STY, 4 CL DepEd Standard School Building	6,168,506.72	2015	DepEd budget	4
Construction of 2 STY, 4 CL AusAid Building Type	5,805,365.90	2014	AusAid Fund	4
Construction of 2 STY, 8 CL Totie S. Paredes Building	6,400,000.00	2012	City School Board	2009 2 sty 8 cl lgu bldg 8 6,400,000.00
Construction of 1 STY, 2 CL FVR 2000 Building	381,633.34	2000	DepEd Budget	fvr 2000 2 190816.67 per room
Construction of 1 STY, 1 CL Pre-School/Kindergarten Building	684,573.41	2011	DepEd budget	2011 deped bldg cost 1 684,573.41
Construction of 1 STY, 1 CL Pre-School/Kindergarten Building	684,573.41	2011	DepEd budget	2011 deped bldg cost 1 684,573.41
Construction of 1 STY, 1 CL Pre-School/Kindergarten Building	684,573.41	2011	DepEd budget	2011 deped bldg cost 1 684,573.41
Construction of 1 STY, 2 CL FVR 2000 Building	381,633.34	2000	DepEd Budget	2011 deped bldg cost 2 684,573.41
Construction of 1 STY, 2 CL FVR 2000 Building	381,633.34	2000	DepEd Budget	fvr 2000 2 190816.67 per room
Construction of 1 STY, 2 CL FFCCII Building	444,444.56	2010	Private Sector Funded	500k BOD Bldg in 1995 (7m x 2 9m) 7936.51 per sqm

Construction of 1 STY, 1 CL Multi-Purpose Workshop Building	395,000.00	2006	DepEd budget	1 similar,
Construction of 1 STY, 1 CL Industrial Arts Building	395,000.00	2005	DepEd budget	1 similar
Construction of 1 STY, 3 CL FVR 2000 Building	572,450.01	2000	DepEd Budget	fvr 2000 3 190816.67 per room
Construction of 1 STY, 3 CL Bagong Lipunan Sch. Building Type I	971,700.00	1975	DepEd budget	3 bl bldg cost 3 323900
Construction of 1 STY, 3 CL Bagong Lipunan Sch. Building Type II	971,700.00	1975	DepEd budget	3 bl bldg cost 3 323900
Construction of 1 STY, 1 CL School Stage (NEW)		2018	Provincial Board	1
Construction of 2 STY, 6 CL City School Building	7,486,959.94	2018	City School Board	6 school record
Construction of 2 STY, 6 CL City School Building	8,089,017.97	2020	City School Board	6 school record
Construction of 4 STY, 8 CL DEPED STANDARD BUILDING	17,285,570.67	2019	DEPED BUDGET	8 school record
Construction of 4 STY, 12 CL DEPED STANDARD BUILDING	44,917,187.60	2019	DEPED BUDGET	12 CO

Construction of 4 STY, 16 CL DEPED STANDARD BUILDING	50,325,135.84	2019	DEPED BUDGET	16 CO
Construction of 2 STY, 8 CL TOTIE S. PAREDES	6,400,000.00	2009	LGU FUNDED	8 school record
Construction of 2 STY, 4 CL DEPED SCHOOL BUILDING	4,932,807.35	2012	DEPED BUDGET	4 similar, Ides
Construction of 2 STY, - CL ADMIN BUILDING	15,074,202.90	2012	DEPED BUDGET	0 school record
Construction of 2 STY, 6 CL PPP BUILDING 2	13,077,573.10	2013	DEPED BUDGET	6 school record
Construction of 1 STY, 1 CL SCHOOL CANTEEN	130,217.00	2019	DEPED BUDGET	1 school record
Construction of 1 STY, 2 CL GUIDANCE OFFICE	1,500,000.00	2018	DEPED BUDGET	2 school record
Construction of 1 STY, 1 CL MEDICAL CLINIC	207,296.00	2014	DEPED BUDGET	1 school record
Construction of 1 STY, 6 CL FVR PHIL 2000	869,000.00	2000	DEPED BUDGET	6 school record
Construction of 1 STY, 4 CL FVR PHIL 2000	647,800.00	2000	DEPED BUDGET	4 school record
Construction of 1 STY, 1 CL BAGONG LIPUNAN	323,900.00	2019	DEPED BUDGET	1 school record
Construction of 2 STY, 4 CL PPP BUILDING 4	7,787,825.76	2015	DEPED BUDGET	4 school record

Construction of 1 STY, 1 CL DEPED BUILDING	395,000.00	2005	DEPED BUDGET	1 similar,
Construction of 1 STY, 2 CL DEPED BUILDING	1,058,938.61	2006	DEPED BUDGET	2 similar, JHS
Construction of 2 STY, 4 CL MALIKSI BUILDING	4,932,807.35	2010	LGU FUNDED	4 similar, Ides
Construction of 2 STY, 4 CL ENRILE BUILDING	4,932,807.35	2010	SENATE FUNDED	4 similar, Ides
Construction of 2 STY, 14 CL TWO STOREY	1,389,255.12	1988	DEPED BUDGET	14 school record
Construction of 2 STY, 4 CLESF BUILDING	2,154,309.52	1990	DEPED BUDGET	4 school record
Construction of 4 STY, 20 CL DEPED STANDARD BUILDING	48,451,608.68	2019	DEPED BUDGET	20 school record
Construction of 1 STY, 1 CL FVR PHL 2000	323,000.00	2000	DEPED BUDGET	1 school record
Construction of 1 STY, 3 CL OLD MUSIC ROOM	604,350.00	1975	DEPED BUDGET	3 school record
Construction of 1 STY, 4 CL FVR PHL 2000	350,000.00	2000	DEPED BUDGET	4 school record
Construction of 2 STY, 4 CL PPP BUILDING 5	7,787,825.76	2015	DEPED BUDGET	4 school record

Construction of 3 STY, 12 CL TOTIE S. PAREDES BLDG 2	14,973,924.00	2017 LGU FUNDED	12 1247826.657
Construction of 4 STY, 20 CL DepEd Building	31,102,890.27	2017 National	20 CO <i>4</i>
Construction of 2 STY, 8 CL PPP Building 1	15,575,651.51	2013 National	8 PSIP CO
Construction of 2 STY, 8 CL PPP Building 3	15,575,651.51	2015 National	8 PSIP CO
Construction of 2 STY, 4 CL DepEd Building	4,932,807.35	2012 National	4 similar, Ides
Construction of 3 STY, 6 CL DepEd Building	10,342,131.51	2015 National	6 2016 6 cl average cost
Construction of 2 STY, 4 CL DepEd Building	4,932,807.35	2011 National	4 similar
Construction of 4 STY, 8 CL Deped Standard Building	21,379,508.64	2019 DepEd Budget	8 CO
Construction of 2 STY, 4 CL AusAid Building	5,678,000.00	2014 AusAid	4
Construction of 2 STY, 4 CL Deped Standard Building	6,479,164.77	2013 DepEd Budget	4
Construction of 1 STY, 2 CL LGU Building	1,063,915.84	2007 LGU	2 2014 lgu bldg

2018 lggu bldg cost per rm
12 1247826.657

4

2018 lggu bldg cost per rm
12 1247826.657

Construction of 1 STY, 2 CL Deped Standard Building	1,058,938.61	2011 DepEd Budget	2
Construction of 1 STY, 2 CL LGU Building	1,063,915.84	1996 LGU	2 2014 Igú bldg
Construction of 2 STY, 4 CL Deped Standard Building	4,607,204.35	2005 DepEd Budget	4 school record
Construction of 1 STY, 4 CL JICA Building		1994 JICA	4
Construction of 1 STY, 1 CL LGU Building	6,400,000.00	2008 LGU	1 2009 Igú bldg
Construction of 4 STY, 12 CL DepEd Building	24,514,577.98	2016 DepEd Budget	12 CO
Construction of 4 STY, 8 CL DepEd Building	14,897,518.84	2017 DepEd Budget	8 CO
Pasong Kawayan II West ES	31,252,400.65	2017 DepEd Budget	12 CO
Mary Cris ES	31,140,220.85	2017 DepEd Budget	12 CO
Gen. Gregorio S. Alona, Sr. MES	25,795,047.81	2017 DepEd Budget	8 CO
Gen. Trias MES	30,949,798.90	2017 DepEd Budget	12 CO
Javalera ES	34,037,208.04	2017 DepEd Budget	16 CO

Tapia ES	17,018,604.02	2017	DepEd Budget	8 CO
Manggahan ES	16,839,680.74	2017	DepEd Budget	8 CO
Pasong Kawayan II ES	16,899,329.44	2017	DepEd Budget	8 CO
Gen. Artemio Ricarte MS	33,631,719.48	2017	DepEd Budget	8 CO
Navarro ES	16,815,859.74	2017	DepEd Budget	8 CO
BUENAVISTA ES	31,102,890.27	2018	DepEd Budget	CO
GOV. FERRER MNHS (MAIN)	53,404,938.84	2018	DepEd Budget	CO
GOVERNOR FERRER MEMORIAL NATIONAL HIGH SCHOOL (BUENAVISTA ANNEX)	22,352,343.62	2018	DepEd Budget	CO
JULIANO C. BROAS ES	22,152,343.62	2018	DepEd Budget	8 CO
LUIS Y. FERRER JR. WEST NATIONAL HIGH SCHOOL	14,897,518.84	2018	DepEd Budget	8 CO
LUIS Y. FERRER, JR. NORTH NATIONAL HIGH SCHOOL	22,152,343.62	2018	DepEd Budget	8 CO
PASONG CAMACHILE ES	10,517,131.51	2018	DepEd Budget	CO
PASONG KAWAYAN II ES	14,897,518.84	2018	DepEd Budget	8 CO

SAN FRANCISCO ES	14,897,518.84	2018	DepEd Budget	8 CO
SANTIAGO ES	22,152,343.62	2018	DepEd Budget	12 CO
SHS IN GEN. TRIAS	29,795,037.68	2018	DepEd Budget	8 CO
SUNNY BROOKE ELEMENTARY SCHOOL	31,102,890.27	2018	DepEd Budget	12 CO
BUENAVISTA ES	31,102,890.27	2017	DepEd Budget	20 CO
GOV. FERRER MNHS (MAIN)	53,404,938.84	2017	DepEd Budget	32 CO
GOVERNOR FERRER MEMORIAL NATIONAL HIGH SCHOOL (BUENAVISTA ANNEX)	22,352,343.62	2017	DepEd Budget	12 CO
JULIANO C. BROSAS ES	22,152,343.62	2017	DepEd Budget	12 CO
LUIS Y. FERRER JR. WEST NATIONAL HIGH SCHOOL	14,897,518.84	2017	DepEd Budget	8 CO
LUIS Y. FERRER, JR. NORTH NATIONAL HIGH SCHOOL	22,152,343.62	2017	DepEd Budget	12 CO
PASONG CAMACHILE ES	10,517,131.51		DepEd Budget	6 CO
PASONG KAWAYAN II ES	14,897,518.84	2017	DepEd Budget	8 CO
SAN FRANCISCO ES	14,897,518.84	2017	DepEd Budget	8 CO

Construction of 2 STY, 6 CL GABALDON SCHOOL BUILDING	4,899,414.27	1920	DEPED BUDGET
Construction of 2 STY, 6 CL DEPED STANDARD BUILDING	3,175,000.00	1991	DEPED BUDGET
Construction of 3 STY, 6 CL DEPED STANDARD BUILDING	10,267,131.51	2016	DEPED BUDGET
Construction of 4 STY, 8 CL DEPED STANDARD BUILDING	22,736,362.12	2019	DEPED BUDGET
Construction of 4 STY, 8 CL DEPED STANDARD BUILDING	22,736,362.12	2019	DEPED BUDGET
Construction of 1 STY, 2 CL PUBLIC;PRIVATE PARTNERSHIP	2,666,261.93	2014	DEPED BUDGET
Construction of 1 STY, 1 CL DEPED STANDARD BUILDING	607,021.40	2010	DEPED BUDGET
Construction of 1 STY, 2 CL FVR 2000 BUILDING	381,633.34	1998	DEPED BUDGET
Construction of 2 STY, 6 CL MUNICIPALITY BUILDING	6,936,881.03	2016	LGU FUNDED
Construction of 2 STY, 6 CL MUNICIPALITY BUILDING	6,936,881.03	2016	LGU FUNDED
Construction of 1 STY, 1 CL DEPED STANDARD BUILDING	500,000.00	1996	DEPED BUDGET

SANTIAGO ES	22,152,343.62	2017	DepEd Budget	12 CO
SHS IN GEN. TRIAS	29,795,037.68	2018	DepEd Budget	16 CO
SUNNY BROOKE ELEMENTARY SCHOOL	31,102,890.27	2016	DepEd Budget	20 CO
Pasong Kawayan II West ES	31,252,400.65	2018	DepEd Budget	12 CO
Mary Cris ES	31,140,220.88	2018	DepEd Budget	12 CO
Gen. Gregorio S. Alona, Sr. MES	25,795,047.81	2018	DepEd Budget	8 CO
Gen. Trias MES	30,949,798.90	2018	DepEd Budget	12 CO
Javalera ES	34,037,208.04	2018	DepEd Budget	8 CO
Tapia ES		2018	DepEd Budget	8 CO
Manggahan ES	16,839,680.74	2018	DepEd Budget	8 CO
Pasong Kawayan II ES	16,899,329.44	2018	DepEd Budget	8 CO
Gen. Artemio Ricarte MS/Navarro ES	33,631,719.48	2018	DepEd Budget	16 CO
JULIANO C. BROSAS ES	16,927,372.89	2019	DepEd Budget	8 CO

SUNNY BROOKE ES	33,481,331.51	2019	DepEd Budget	12 CO
GOVERNOR FERRER MEMORIAL INTEGRATED NATIONAL HIGH SCHOOL	118,583,047.84	2020	DepEd Budget	40 CO
Ipilan Barrio School	24,891,000.00	2021	DepEd Budget	8 CO